

N
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Co.

Complete Address: Box 287, Great Bend, Kansas

Lease Name W. M. Miller Well No. 4

Location SW SW NE Sec. 3 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3384'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co., Inc.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 1:30 Day 19 Month November Year 1962

The Above well was plugged as follows:

Hole filled with sand to 3350' and cemented with 5 sacks.

7" casing pulled. 5 1/2" casing pulled to 150' and 30 sacks cement

pumped thru 5 1/2" casing at 150'. Hole filled with mud to 35'.

Rock bridge set from 35' to 25' and hole cemented to bottom of cellar

with 50 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1962

I hereby certify that the above ^{CONSERVATION DIVISION} well was plugged as herein stated.
Wichita, Kansas

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 11/27/62

INV. NO. 6044-u