



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

June 1, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 8 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Pat Simmons

Complete Address: 5252 N. Broadway, Wichita, Kansas 67219

Lease Name: Renolett Well No. 2

Location: NW SW SW Sec. 5 Twp. 21 Rge. 6 (E) (W) X

County: Rice Total Depth 3533' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:


Fill hole with sand to 3475' and cement with 5 sacks cement.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 35 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent