



15.159.04368.0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1968
CONSERVATION DIVISION
Wichita, Kansas

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 10, 1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orville Powell of Braden-Deem, Inc. has this date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: P.O. Box 129, Sterling, Kansas 67579

Lease Name: Johnson "A" Well No. 3

Location: SE NW NE Sec. 4 Twp. 21 Rge. 6 (E)(W) X

County: Rice Total Depth 3450' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Powell was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement hole with 30 sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent