



15.159.04363.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 16, 1965

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1965

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Cobas this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name: Cleavinger Well No. 1

Location: SW SW NW Sec. 4 Twp. 21 Rge. 6 (S) (W) X

County Rice Total Depth 3471' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3415' and cement with 5 sacks.

Fill hole with mud to 160'. Set rock bridge from 160' to

150' and cement hole with 25 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with 10

sacks cement.

Very truly yours,

William L. Mitchell
Conservation Division Agent