



15.159.04369.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 9, 1965

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name: Cleavinger Well No. 4

Location: SE SW NW Sec. 4 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3471' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Push 5 1/2" plug to 3410'. Fill hole with sand to 3400' and
cement with 5 sacks. Fill hole with mud to 160'. Set rock
bridge from 160' to 150' and cement hole with 20 sacks.
Fill hole with mud to 40'. Set rock bridge from 40' to 30'
and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent