



15.159.05255.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
June 14, 1966 CORPORATION COMMISSION

JUN 20 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: P.O. Box 127, Sterling, Kansas

Lease Name: Cleavinger Well No. 5

Location: NE NW NW Sec. 4 Twp. 21 Rge. 6  (W)  X

County Rice Total Depth 3430' Oil Well  X

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 5 sacks.

Fill hole with mud to 190'. Set rock bridge from 190' to 180' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent