

State of Kansas



15.159.04362.0000

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg.  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 12 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

October 31, 1968

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Plains Exploration Company

Complete Address: 1135 Petroleum Club Bldg., Denver, Colorado 80202

Lease Name: Alexander Well No. 1

Location: SE NE NW Sec. 4 Twp. 21 Rge. 6 (E) (W) X

County: Rice Total Depth 3472' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent