

State of Kansas



RECEIVED
OCT 22 1968
CONSERVATION DIVISION
Wichita, Kansas

15.159.05253.0000

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

October 15, 1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Plains Exploration Company

Complete Address: 1135 Petroleum Club Bldg., Denver, Colorado 80202

Lease Name: Alexander Well No. 2

Location: NW NE NW Sec. 4 Twp. 21 Rge. 6 (E)(W) X

County: Rice Total Depth 3460' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

(Tubing in hole and hole bridged over at 1170')

Dump 5 sacks cement on bridge at 1170'. Fill hole with mud to 210'.

Set rock bridge from 210' to 200' and cement with 25 sacks. Fill hole

with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10

sacks cement.

Very truly yours,

A handwritten signature in cursive script, appearing to read "William J. Roman".
Conservation Division Agent