



15.159.04350.0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

RECEIVED
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202
 DECEMBER 2 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

November 23, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Esendosa of Braden-Deem, Inc. has this date requested permission to plug the following described well:

Mr. Esendosa guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: P.O. Box 129, Sterling, Kansas 67679

Lease Name: Miller "B" Well No. 3

Location: SW NE NW Sec. 3 Twp. 21 Rge. 6 (E)(W) X

County: Rice Total Depth 3418' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Esendosa was instructed to plug the well as follows:

Fill hole with sand to 3360' and cement hole with 5 sacks cement.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 50 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 15 sacks cement.

Very truly yours,

William J. Loman
 Conservation Division Agent