



15.159.04353.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B HARVEY Secretary
E. EDWARD JOHNSON Gen Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 22, 1965

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co has this
date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: P.O. Box 127, Sterling, Kansas

Lease Name: Miller Well No. 4

Location: NE SW NW Sec. 3 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3430' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3360' and cement with 5 sacks.

Fill hole with mud to 160'. Set rock bridge from 160' to

150' and cement hole with 30 sacks. Fill hole with mud to

30'. Set rock bridge from 30' to 20' and cap hole with 10

sacks cement.

Very truly yours,

William J. Roman
Conservation Division Agent