



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 22, 1970

VERBAL PERMIT FORM.
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Commercial Oil Company

Complete Address: 5252 N. Broadway, Wichita, Kansas 67219

Lease Name: Rainey Well No. 3

Location: NW SE SE Sec. 3 Twp. 21 Rge. 6 (E)(W) X

County: Rice Total Depth 3393' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3350' and cement with 5 sacks cement.

(5 1/2" and 7" casing coming out together--decided not to try to pull either string) Set rock bridge from 250' to 235' and dump 2 sacks cement on bridge.

Let set overnight. Shoot 7" & 5 1/2" casing at 200' and circulate with 250 sacks Poz-mix.

Very truly yours,


Conservation Division Agent