

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN 4 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Socony Mobil Oil Company, Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name R. C. Gates Well No. # C-7

Location NE SE SE Sec. 34 Twp. 21 Rge. 13 (E) (W)W

County Stafford Total Depth 3706'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30AM Day 3rd Month June Year 1965

The Above well was plugged as follows:

285' of 8 5/8" surface pipe, cement circulated. 3703' of 5 1/2" long string,  
no cement record. Plug back to 3512'. Top perferation 3407'. Bottom of  
hole was sanded to 3300', and cemented with 5 sacks. 2530' of 5 1/2" long  
string was recovered from the hole. Fluid level was up in the hole.  
Bridge plug was pushed in fluid to 270', and 20' of rock and sand bridge  
on plug at 270'. 10 sacks of cement was mixed in barrel and put on plug  
at 250', through the dump bailer, and let set over-night. Next morning  
hole was bailed dry, and 15 sacks of cement was added to the plug. Hole  
was filled with mud to 40', and 10' of rock bridge, and cemented with 10  
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6-4-65

INV. NO. 1271-W