

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued May 8, 1967.

Operator's Full Name Mobil Oil Company

Complete Address: P. O. Box 1828, Oklahoma City, Oklahoma

Lease Name M. Gates Well No. # 1

Location NE NE NE Sec. 34 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3652'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 1:00PM Day 26th Month May Year 1967

The Above well was plugged as follows:

248' of 13 3/8" surface pipe, cemented with 250 sacks. 3648' of 7" long
string, cemented with 300 sacks. Plug back T.D. 3597'. Top perferation
3312'. Bottom of the hole was sanded to 3250', and cemented with 7 sacks,
through the dump bailer. 1700' of 7" long string was recovered from the hole.
Bridge plug was pushed in fluid to 240', bridge plug and rock bridge from 240'
to 230'. 10 sacks of cement was mixed in a barrel, and put on plug at 230',
through the dump bailer, and let set over-night. Next day hole was bailed dry
and 40' sacks of cement was added to the plug. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 25 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5-29-67

INV. NO. 5295-W