

K
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued May 8, 1967.

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mobil Oil Company

Complete Address: P. O. Box 1828, Oklahoma City, Oklahoma

Lease Name M. Gates Well No. # 2

Location SE NE NE Sec. 34 Twp. 21 Rge. 13 (E) W

County Stafford Total Depth 3660'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 11:30AM Day 13th Month May Year 1967

The Above well was plugged as follows:

260' of 13 3/8" surface pipe, cemented with 260 sacks. 3653' of 7" long string,
cemented with 300 sacks. This is an open hole. Bottom of the hole was sanded
to 3600', and cemented with 7 sacks. 1710' of 7" long string was recovered
from the hole. Bridge plug was pushed in fluid to 250', bridge plug and rock
bridge from 250' to 235'. 10 sacks of cement was mixed in a barrel, and put
on plug at 235', through the dump bailer, and let set over-night. Next day
hole was bailed dry, and 40 sacks of cement was added to the plug. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 25
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/15/67

INV. NO. 5211-W