

15.185.01826.0000

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 11 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued May 8, 1967.

Operator's Full Name Mobil Oil Company

Complete Address: P. O. Box 1828, Oklahoma City, Oklahoma

Lease Name M. Gates Well No. # 4

Location SE SE NE Sec. 34 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3680'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 11:30AM Day 9th Month May Year 1967

The Above well was plugged as follows:

235' of 10 3/4" surface pipe, cemented with 275 sacks. 3676' of 7" long  
string, cemented with 300 sacks. This is an open hole. Bottom of the hole  
was sanded to 3650', and cemented with 7 sacks. 1700' of 7" long string  
was recovered from the hole. Bridge plug was pushed in fluid to 225',  
bridge plug and rock bridge from 225' to 215'. 10 sacks of cement was mixed  
in a barrel, and put on plug at 215', through the dump bailer, and let set  
over-night. Hole was bailed dry, and 20 sacks of cement was added to the  
plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and  
cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 5/11/67  
INV. NO. 5201-W

Signed: Audie Elving  
Well Plugging Supervisor