

74
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Socony Mobil Oil Company, Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name R. C. Gates Well No. # B-6

Location NE NE SE Sec. 34 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3696'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30AM Day 27th Month May Year 1965

The Above well was plugged as follows:

275' of 10 3/4" surface pipe, cement circulated. 3686' of 7" long
string, cemented with 200 sacks. Plug back to 3595'. Top perferation
3359'. Bottom of the hole was sanded to 3290', and cemented with 5 sacks.
1830' of 7" long string was recovered from the hole. Fluid level in the
high. Bridge plug was pushed in fluid to 265', and 15' of rock bridge on
plug. 6 sacks of cement was mixed in barrel, and put on plug at 250',
through the dump bailer, and let set over-night. Next morning hole was
bailed dry, and 24 sacks of cement was added to the plug. Hole was filled
with mud to 40', and 10' of rock bridge, and cemented with 15 sacks to
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/28/65

INV. NO. 1236-11