

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- Authority May 20, 1981

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name J. A. Allison

Complete Address Suite 305, 300 W. Douglas, Wichita, KS

Lease Name Van Doren Well No. 1

Location C. Sw. SE. Sec. 4 Twp. 21 Rge. 35 (East) (West)

County Rearny Total Depth 5050

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. 683

Operation Completed: Hour: 12:30 PM Day: 28 Month: May Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There was 285' of 8 1/8" surface casing. C.C.
5 1/2" casing set to 46'94". Plug back 46'45"
Perforations were 46'18" - 46'10". 1st Plug on
bottom with 50 lbs cement. 2nd Plug
at 1400' with 35 lbs cement. 10 lbs fell. 3rd
Plug at 900' with 35 lbs cement. 15 lbs fell
released plug. 4th plug at 750' with 50 lbs
cement. 5 lbs fell. 5th plug at 400' with 10 lbs
cement. There was 2820' of 5 1/2" salvaged

I hereby certify that the above well was plugged as herein stated.

all plugs 50/50 for 20% fall
3% chloride. Accomplished
by Sun Cementing. Signed: Lawrence Thomas
Conservation Division Agent
DATE 6-23-81
INV. NO. 5629-w

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1981
CONSERVATION DIVISION
Wichita, Kansas