

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Authority to plug issued
Nov-12, 1975 -
12-18-75

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kaiser - Francis
Complete Address 4120 East 51st St. Tulsa, Okla 74135
Lease Name Michals "B" Well No. 1
Location NE SE NE Sec. 16 Twp. 21 Rge. (E) (W) 34
County Jummy Total Depth 4920
Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated
Plugging Contractor Richard Engineering
Address Great Bend, Kans. License No. 670
Operation Completed: Hour 12:15 PM Day 16 Month Dec Year 1975

The above well was plugged as follows:

There was 522' of 8 1/8" surface casing
4 1/2" set to 4918'. Perforations were from
4720 - 4716'. 1st plug at 4900' with 15
sacks cement and 2 sacks cotton seed hulls.
2nd plug at 900' with 50 sacks cement,
10 sacks fcll. 3rd plug at 500' with 35 sack
Cement, 10 sacks of fcll. 4th plug at 40-0
with 15 sacks cement. There was 1480' of

I hereby certify that the above well was plugged as herein stated.
4 1/2" salvage. Plug were
pumped by Sun Cementing
Great Bend, Ks.
Signed: Quence Thomas
Well Plugging Supervisor

INVOICED

DATE 12-18-75

INV. NO. 2434-W