

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.185.30275.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michael of Sage Drilling Company has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name: Sipes Well No. # 1

Location: SW SE SW Sec. 22 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3721' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Michael was instructed to plug the well as follows:

286' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with 1/4 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sack

Very truly yours,

Archie Elving