



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Stone of Cheyenne Exploration Inc has this date requested permission to plug the following described well:

Mr. Stone guarantees payment of the plugging fee.

Operator's full Name: Cheyenne Exploration Inc.

Complete Address: 357 Lulu Wichita, Ks

Lease Name: Schulz Well No. 3

Location: NE/NW/SE Sec. 22 Twp. 21 Rge. 13 (E)(W) W

County: Stafford Total Depth 3770 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stone was instructed to plug the well as follows:

300 ft 8 5/8 surface pipe cemented with 200 sacks. Pump
100 sacks cement to 580 ft. 2nd plug at 300 ft with 20
sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks
cement to surface. 2 sacks cement in rat hole.

Pumped by Dowell Chemical Co. Great Bend, Ks

Very truly yours,


Conservation Division Agent