



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1973
CONSERVATION DIVISION
Wichita, Kansas

10-5-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Tesoro has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Tesoro Petroleum Corp.

Complete Address: 8520 Crownhill, San Antonio, Texas.

Lease Name: Marion Well No. 1-10

Location: SE NW Sec. 10 Twp. 21 Rge. 38 YY (E) (W)

County: Kearny Total Depth 3870' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 322' circulated w/ cement . 5 1/2" casing to 3870' cemented.


Top perforations 3804' Plug bottom w/ 20 sacks cement.

Top of cement 3650' Mud 3650' to 320'

Spot 35 sacks cement 320' to 220' Mud 220' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent