

TYPE

AFFIDAVIT OF COMPLETION FORM

KERR #1 OWWO ACO-1 WELL HISTORY-

(Formerly Pickrell/SW Petro-Chem Kerr "A" #1)

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP _____

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F _____ Letter requesting confidentiality attached.

C _____ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5171 EXPIRATION DATE 6/30/84

OPERATOR TXO Production Corp. API NO. 15-097-20,213A-0001

ADDRESS 200 W. Douglas, Ste. 300 COUNTY Kiowa

Wichita, KS 67202 FIELD Wildcat

** CONTACT PERSON Harold R. Trapp PROD. FORMATION dry

PHONE (316) 265-9441 no Indicate if new pay.

PURCHASER plugged LEASE Kerr

ADDRESS plugged WELL NO. #1 OWWO (formerly Pickrell-

Kerr "A" #1)

WELL LOCATION C SW NW

DRILLING Freeman, Rig #1 1980 Ft. from North Line and

CONTRACTOR 251 N. Water, Ste. 10 660 Ft. from West Line of

ADDRESS Wichita, KS 67202 the NW (Qtr.) SEC 17 TWP 28SRGE 18 (W).

PLUGGING Clarke Oil Field Services

CONTRACTOR 107 W. Fowler

ADDRESS Medicine Lodge, KS 67104

WELL PLAT

(Office Use Only)

KCC

KGS

SWD/REP

PLG.

NGPA _____

TOTAL DEPTH 4920 PBD 4840

SPUD DATE 4-23-83 DATE COMPLETED P&A 7-28-83

ELEV: GR 2239 DF none KB 2251

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING

USED TO DISPOSE OF WATER FROM THIS LEASE hauled

Amount of surface pipe set and cemented 8-5/8"@238 DV Tool Used? no

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, (Dry) Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion. Other completion. NGPA filing.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

I, Harold R. Trapp, being of lawful age, hereby certifies that:


I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Handwritten signature of Harold R. Trapp

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 15th day of August

19 83.



Handwritten signature of Bonnie J. Holcomb

(NOTARY PUBLIC)

MY COMMISSION EXPIRES: 12-23-85

STAMP: RECEIVED OPERATIONS COMMISSION

8-17-83

** The person who can be reached by phone regarding any questions concerning this information.

STAMP: AUG 17 1983 CONSERVATION DIVISION Wichita, Kansas

Side TWO

OPERATOR TXO PROD. CORP.

LEASE NAME Kerr

SEC 17 TWP 28S RGE 18 (E) (W)

WELL NO #1 OWWO

FILL IN WELL INFORMATION AS REQUIRED;

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc. Top Bottom Name Depth

XX Check if no Drill Stem Tests Run. XX Check if samples sent Geological Survey. RAN O.H. LOGS			LOG TOPS	
			Herington	2468 -217
			Cottonwood	2998 -741
			Lansing	4252 -2001
			Stark	4502 -2251
			B/K.C.	4657 -2406
			Cong.	4834 -2583
			Miss.	4845 -2594
			RTD	4920
			LTD	4920
		PBD	4840	

If additional space is needed use Page 2

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface (Pickrell-Kerr A)	#1	8-5/8		238'		135	
Prod.-new		4-1/2	10.5#	4919'	Class A	150	2% KCLH2O w/10% salt + 75% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none	none	none	4 JSPF (37 h.)	Miss.	4846-64'
TUBING RECORD			4 JSPF (40 h.)	Cherokee	4818-28'
Size	Setting depth	Pecker set at			
2-3/8"	4810				

ACID, FRACTURE, SHOT, CEMENT-SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/1500 gals 15% HCl w/FE agent, cla-sta, surfactant & 35 BS	4846-64'
CIBP @4840'	
Treat w/750 gals 15% NE w/additives	4818-28'

Date of first production 7-28-83	Producing method (flowing, pumping, gas lift, etc.) dry	Gravity none
Estimated Production-I.P. show	Oil none	Water none
Disposition of gas (vented, used on lease or sold) 1/2 & A	Gas none	Gas none

4818-28'
Perforations

Sun Oilwell Cementing
A Division of BJ Hughes, Inc.

P. O. Box 169
GREAT BEND, KANSAS 67530

CEMENTING TICKET
and Invoice Number No. 15769

Date: 8-5-83 Customer Order No.: Sec: 17 Twp: 28 S Range: 18 W Truck Called Out: 8:00 AM On Location: 9:30 AM Job Began: 9:45 AM Job Completed: 10:30 AM

Owner: Texas Oil Gas Contractor: Charge To: Texas Oil Gas

Mailing Address: City: State:

Well No. and Farm: Ken #1 Place: 542183 J + Van E. Co. County: Kiowa State: Kansas

Depth of Well: Depth of Job: Casing { New Size: Used Weight: } Size of Hole Amt. and Kind of Cement: Cement Left in casing by: Request: Necessity: feet

Kind of Job: Plug to Abandonment OW: Drillpipe: { Rotary Cable: } Truck No.: #31

Condition of Well at time of Cementing: Type of Plugs:

Pressure Circulating: Minimum: Maximum: 0

Time Required Mixing Cement: min. Making Change: min. Pumping Cement: min.

Remarks: Mixed 20 sk 100 lb P.C. 37 C. 1 2 70 ml down 5 sk to cement backside to top of ground

Price Reference No.: 10
Price of Job:
Second Stage:
Standby Truck:
Other Charges:
Pump Truck Mileage: 48.00

Cementer: Bob Baker Material Left on Location: 8 1/2 Head (M.L.)

Helper: Dale District: Great Bend State: Kansas

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.
State Pluggers on Location: Yes No
Signature: J. L. [unclear] Agent of Contractor or Operator

SALES TICKET FOR MATERIALS

QUANTITY, SACKS	BRAND AND TYPE	PRICE	TOTAL
120	Common Used sk		
80	P.C. (Used) sk		
Ce. Cl.:	511 #1		
AM. Cl.:			
Gal:	344 #1		
Plugs:	NO		
	Handling and Dumping		
Delivered by Truck No.:	T-35	Mileage: 32	
Delivered From:	Medicine	Sales Tax:	
Signature of Operator:	Rovaty	Total Charges:	

Sun Oilwell Cementing
A Division of BJ-Hughes, Inc.

P. O. Box 169
GREAT BEND, KANSAS 67530

CEMENTING TICKET No. 15782
and Invoice Number

Date: 8-4-83 Customer Order No.: 17-28-18 Truck Called Out: 1:00 PM On-Location: 3:30 PM Job Began: 3:50 AM Job Completed: 4:30 PM

Owner: T.X.O. Contractor: CLARKE WELL SERVICE Charge To: T.X.O.

Mailing Address: City: State:

Well No. and Farm: KERR #1 Place: 54-183 NW 1/4 E-S County: KIOWA State: KANSAS

Depth of Well: 4920 Depth of Job: 1160 Casing: { New Size: 7 7/8 Used Weight: 90 } Size of Hole: 7 7/8 Amt. and Kind of Cement: 90 Cement Left in casing by: Request: Necessity: feet

Kind of Job: PLUG OW: Drillpipe: 2 7/8 { Rotary Cable } Truck No.: 30

Condition of Well at time of Cementing: D-A Type of Plugs:

Pressure Circulating: Minimum: Maximum:

Time Required Mixing Cement: min. Making Change: min. Pumping Cement: min.

Remarks: MIXED 40 SKS AT 1160 PULLED UP TO 450' MIXED 40 MORE SKS. CEMENTED WITH 80 SKS 6 3/4 40 LB 3 1/2" CCLL 290 GEL. #9 350.00 48.00 THANK YOU

Cement: HAMMER Material Left on Location:

Helper: STEVE District: GREAT BEND State: KANSAS

The above job was done under supervision of the owner, operator, or his agent whose signature appears below. State Plugger on Location: Yes No Signature: Eli H. M... Agent of Contractor or Operator

Prices Subject to Correction.

SALES TICKET FOR MATERIALS

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
48	Common		
32	Pop mix		
cc cl: 206			
AM. CL:			
Ge. 138			
Plugs:			
Delivered by Truck No.: B-25	Handling and Dumping:		
Delivered From: GREAT BEND	Mileage: 32		
Signature of Operator: STAN W	Sales Tax:		
	Total Charges:		