

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

to AE Information Completely
to Required Affidavit
to or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

McPHERSON County, Sec. 20 Twp. 21 Rge. 1 (E) (W)
Location as 990' FROM SOUTH LINE AND 2310' FROM EAST LINE
Lease Owner: FLOYD KING
Lease Name: HETZKE "A" Well No. 3
Office Address: LYONS, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed 19
Application for plugging filed APRIL 8 19 65
Application for plugging approved 19
Plugging commenced APRIL 9 19 65
Plugging completed APRIL 27 19 65
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN
Producing formation Depth to top Bottom Total Depth of Well 3319 Feet
Show depth and thickness of all water, oil and gas formations.

CIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13"	129'	NONE
				7"	3213	1700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

SANDED TO 3300' - DUMPED 6 SKS CEMENT-
PULLED CASING-HOLE BRIDGED @ 130'-
DUMPED 4 YDS OF READY MIX CEMENT IN
SURFACE PIPE.

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D CASING PULLING CO. LICENSE #236
Address BOX 422, ELDORADO, KANSAS

STATE OF Kansas COUNTY OF Butler, ss.
Lawrence H. Matthews (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence H. Matthews

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1965

My commission expires July 28, 1967
Mary Bailey Notary Public.

WELL RECORD

15.113.04533.0000

COUNTY: McPherson. SECTION: 20. TOWNSHIP: 21S. RANGE: 1W.

COMPANY OPERATING: Continental Oil Company. ADDRESS: Box 267, Great Bend, Kansas.

FARM NAME: F. A. Hetzke "A". WELL NO: No. 3.

DRILLING STARTED: 11-10-36. DRILLING FINISHED: 12-11-36.

DATE OF FIRST PRODUCTION: 12-19-36.

WELL LOCATED: SW/4 SE/4, 990' N & 330' E of S/4 Corner.

CHARACTER OF WELL: Oil Well.

Formation Record

<u>Formation</u>	<u>Top</u>	<u>Bottom</u>	<u>Remarks</u>
Surface Clay	0	25	
Sand	25	40	
Sandy Lime	40	82	
Shale & Shells	82	300	Set 129'11" of 12 1/2" casing at 137' and cemented w/150 sacks Ideal cement.
Anhydrite	300	350	
Shale & Shells	350	798	
Lime	798	826	
Shale & Shells	826	1648	
Shale	1648	1710	
Broken Lime	1710	1733	
Lime	1733	1768	
Broken Lime	1768	1829	
Lime	1829	1839	
Shale	1839	1904	
Lime	1904	2098	
Shale & Shells	2098	2196	
Broken Lime	2196	2264	
Shale	2264	2298	
Lime	2298	2627	
Shale & Shells	2627	2648	
Broken Lime	2648	2693	
Sticky Shale & Shells	2693	2758	
Broken Lime	2758	2794	
Lime Shells & Shale	2794	2833	
Shale & Shells	2833	2872	
Shale	2872	2888	
Chat	2888	3067	
Lime	3067	3110	
Shale	3110	3122	
Lime	3122	3183	
Shale	3183	3193	
Sticky Shale & Shells	3193	3220	
Broken Lime	3220	3271	
Shale	3271	3291	Set 3312'0" of 7" OD casing at 3291' and cemented w/400 sacks Ideal cement.
Lime - Hunton	3291	3329'	

800' oil in hole f/3291-98'.
1500' oil in hole f/3298-3303'.
2000' oil in hole f/3323-25'.

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1965

CONSERVATION DIVISION
Wichita, Kansas