

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

McPherson County. Sec. 20 Twp. 21 Rge. 1 (E) W(W)  
Location as "NE/CNW/SW" or footage from lines NE NW SW  
Lease Owner D. M. Shawver  
Lease Name Hetzke "B" Well No. 1  
Office Address 817 Central Building  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 19  
Application for plugging filed September 21, 1954 19  
Application for plugging approved September 28, 1954 19  
Plugging commenced September 22, 1954 19  
Plugging completed September 28, 1954 19  
Reason for abandonment of well or producing formation Unprofitable production.

If a producing well is abandoned, date of last production July 5, 1954 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Hunton Lime Depth to top 3286' Bottom Total Depth of Well 3321' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hunton Lime	Oil	3286'		8 5/8"	165'	
				5 1/2"	3290'	2852'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand to 3275', dumped 6 sax cement with dump bailer, top of cement 3245'. Filled hole with mud to 150', set rock bridge, cumped 15 sax cement. Top of cement, 105'. Filled with mud to 15', set rock bridge, & dumped 5 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J & M CASING PULLING COMPANY  
Address BOX 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
D. M. SHAWVER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. M. Shawver  
817 CENTRAL BUILDING  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1954

My commission expires March 30, 1957  
Notary Public.

PLUGGING  
FILE SEC 20 T 21 R 16  
BOOK PAGE 65 LINE 25

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - SHAWVER-GRAHAM, INC.  
Farm - A. Hetzke "B" No. 1

SEC. 20 T. 21 R. 1W  
NE NW SW

Total Depth. 3290'

Comm. 4-18-49


Shot or Treated.

Contractor.

Issued. 6-18-49

Comp. 4-28-49

County. McPherson  
KANSAS



CASING:

8 5/8" 165' surface cem. w. 105 sx. reg.  
2 sx. calcium chloride  
5 1/2" 3290' 35 sx. reg.

Elevation. \_\_\_\_\_

Production. 50Bbl. a

Figures Indicate Bottom of Formations.

surface soil & clay	45
shells	60
shells & shale	390
lime shells	435
lime shells & shells	675
lime brkn.	875
shale	1250
shale & shells	1640
lime brkn.	1890
lime	2110
shale & lime	2275
lime brkn.	2385
lime	2685
lime & shale	2790
scale	2915
chat & lime	2990
lime-chert	3008
chert	3028
lime & chert	3081
lime	3178
dolo.	3185
lime	3212
shale	3286
Hunton dolo.	3290
Total Depth	3290

Tops:	
Kansas City	2305
Miss.	2915
Viola	3286

9.22.54

T.D. 3290

8-165


5' - 3290 - 354

624 3285

1554 155

524 top

# 11



RECEIVED  
OCT - 7 1954  
CONSERVATION DIVISION  
Wichita, Kansas