


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

McPherson

County. Sec. 20 Twp. 21 Rge. 1 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW NW SW

Lease Owner D. M. SHAWVER

Lease Name HETZKE "B" Well No. 2

Office Address 817 Central Building

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 19

Application for plugging filed September 21, 1954 19

Application for plugging approved September 22, 1954 19

Plugging commenced September 28, 1954 19

Plugging completed October 2, 1954 19

Reason for abandonment of well or producing formation Unprofitable Production.

If a producing well is abandoned, date of last production September 23 19 54

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Hunton Lime Depth to top 3280' Bottom 3311' Total Depth of Well 3311' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hunton Lime	Oil	3280'	3311'	8 5/8"	153'	
				5 1/2"	3283'	1495'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 6 sax cement @3290', with dump bailer. Top of cement 3260'.
Filled hole with mud to 160', set 10' rock bridge, dumped 15 sax cement.
Top of cement 120'. Filled with mud to 15'. Set rock bridge, dumped
5 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J & M CASING PULLING COMPANY
Address BOX 711, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. M. SHAWVER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. M. Shawver
817 CENTRAL BUILDING
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October 19 54

My commission expires March 30, 1957

Rosemary Penrose
Notary Public.

PLUGGING
FILE SEC 20 T 21 R 1W
BOOK PAGE 65 LINE 24

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

15.113.02036.0000


Company - SHAWVER-GRAHAM
Farm - A. Hotzko No. 2

SEC. 20 T. 21 R. 1W
NE SW NW SW
625' from WL 825' from NL
of SW/4

County. McPherson

KANSAS

Total Depth. 3311
Comr. 5-29-49 Comp. 6-12-49
Shot or Treated.
Contractor.
Issued. 7-23-49



CASING:

3 5/8" 153' com/w/100sx
5 1/2" 3283' com. w/40 sx

Elevation. _____

Production. Est. 75 bbl

Figures Indicate Bottom of Formations.

surface clay	32
sand, red rock	70
shale, shells	365
limo, shale	545
limo, shells, shale	625
shale, shells	685
limo, shale	725
red rock	735
limo, shale	985
shale, shells	1405
shale, limo	1680
shale, shells	1715
shale, limo	1955
limo	2115
limo, shale	2220
limo	2275
shale, limo	2332
limo, K. C.	2670
limo, shale	2750
limo	2761
limo, shale	2914
limo, mississippi	2933
limo, short	2950
limo,	2985
limo, hard	2999
limo	3082
limo, cherty	3088
limo	3208
limo, shale	3252
shale	3280
hunton dolomite	3311
Total Depth	

6 34 3275

TOPS:

Lansing KClimestone	2305
Mississippi Limestone	2914
Hunton Limestone	3280

RECEIVED
KANSAS GEOLOGICAL SOCIETY
OCT - 4 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC 20 T 21 R 1W
WELL 65-1-1-24