

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1973
CONSERVATION DIVISION
Wichita, Kansas
10-5-73

Operator's Full Name Tesoro Petroleum Corp.

Complete Address 8520 Crownhill, San Antonio, Texas 78209

Lease Name Marion Well No. 1-10

Location SE NW Sec. 10 Twp. 21 Rge. 38 (E) (W)

County Kearny Total Depth 3870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Casing Pulling

Address Box 506; Liberal, Kansas License No. 511

Operation Completed: Hour 5:00Pm Day 1 Month 10 Year 1973

The above well was plugged as follows:

8 5/8" to 322' Grouted w/ cement. 5 1/2" to 3870' cemented.

Top perforations 3804' Plug bottom w/ 20 sacks cement.

Top of cement 3650' Mud 3650' to 320'

Spotted 35 sacks cement 320' to 220' Mud 220' to 45'

Plug, H^ulls & 15 sacks cement 45' to 0'. Company Pump

~~6000~~ Pulled 3469' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated

DATE 10/5/73
INV. NO. 4980-W

Signed: [Signature]
Well Plugging Supervisor