

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-12-76
JUL 12 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 093-20,308 (of this well)
Wichita, Kansas

Operator's Full Name Maurice L. Brown Co.
Complete Address 1500 Dickers KSB&T Bldg, Wichita Kans.
Lease Name Campbell Well No. 1
Location C. N.E. SW. Sec 16 Twp. 21 Rge. (E) (W) 35
County Neosho Total Depth 5035
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated

Plugging Contractor Sage Drilling Co, Inc
Address 500 Bitting Bldg, Wichita Ks License No.
Operation Completed: Hour 4:00 AM Day 9 Month July Year 1976

The above well was plugged as follows:

There was 275' of 8 1/8" surface casing.
1st plug at 600' with 50 sacks cement.
Filled with heavy mud to 250'. 2nd
plug at 250' with 35 sacks cement.
Filled with heavy mud to 40. set Bridge.
3rd plug from 40-0 with 15 sacks
cement. 5 sacks in rat hole. Recovery
ished by Halliburton, Liberal, Kans.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed Lawrence Thomas
Well Plugging Supervisor

DATE 7-14-76
INV. NO. 3472-W