

15.113.04539.0000



KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

MAR 12 1962

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: McPherson

Location: NE- NE- SW- Sec. 20 Twp. 21 Rge. I X(E) (W)

Name of Field: Graber Total Depth: 3365'

I have this date completed supervision of plugging of:

Lease Name: Kinderblade Well No. 5

Operator's Full Name: Jenkins-Ray Pipe & Supply Co

Complete Address: P.O. Box 967 Ponca City, Oklahoma

Plugging Contractor Knight Casing Pulling Co

Address: Box 304 Chase, Kansas. License No. 436

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6:PM Day I Month 3 Year 62

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3360' back to 3310' ran 7 sax cement w/ dump bailer.

Shot off and pulled 7" casing. Filled hole w/ mud from 3280" back to 160' set a 10'

rock bridge and filled hole w/ 6 sax ready mix cement from 150' back to zero 5' below

ground level. 10" surface pipe 5' below ground level.

Signed: William Jones  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

**INVOICED**

DATE 3-13-62

INV. NO. 4984-E