

4
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cleary Petroleum Inc.

Complete Address: 310 Kerman Bldg. Okla. City, Okla.

Lease Name Hildebrand Well No. # 1

Location NE NE Sec. 16 Twp. 21 Rge. 38 (E) (W)

County Kearny Total Depth 5087'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling

Address: Liberal, Kansas License No. # 1

Operation Completed: Hour 7 PM Day 17 Month 9 Year 65

The Above well was plugged as follows:

8 5/8"-306' Circulated w/cement. 5 1/2"-5087' Cemented.

Plug bottom w/20 Sax.cement top cement 4800' Mud 4800' to 700'

Spotted 25 Sax.cement 700' to 625' Mud 625' to 325'

Spotted 25 Sax.cement 325' to 250' Mud 250' to 35'

Plug, 10 Sax.cement 35' to 0 Pulled 3400' 5 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

DATE 9/20/65
INV. NO. 1828-W

Signed: [Signature]
Well Plugging Supervisor