

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 125-29LOCATION NW-SE-SESEC. 9 TWP. 21 RGE. 3 WDry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease J. StuckyOperator Shell Oil Co. Address Box 744 St. Bend KansasField _____ County McPhersonTotal Depth 3404 Feet.Plugging Contractor Fisher Casing pulling Co.Plugging Contractor's License No. 49Address Box 221 St. Bend, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 15 1/2" @ 150' C.W.C. Other pipe in well was 8 5/8" @
3260' and 7" @ 3303' Top perf. 2975'. Filled hole back to
2965' and dumped 6 sx of Cem. With dump trailers. Shot off and
pulled 2800' of 7" casing. Filled hole back with sand to 2800'
and dumped 6 sx of Cem. Shot off and pulled 2000' of 8 5/8" casing.
Filled hole with mud to 250' set 10' rock bridge and run
40 sx of Cem. mud to 25' rock bridge and 10 sx of Cem. to
base of cellar. Completed.

STATE CORPORATION COMMISSION

001-20

001-20

Warren H. Horner
 District Conservation Agent

Date 10-26-53