


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW&SW&" or footage from lines Finney County. Sec. 17 Twp. 21S Rge. 33W (E) (W)  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Wampær "A" Well No. 3  
Office Address 780 Fourth National Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 16 19 59  
Application for plugging filed November 16 19 59  
Application for plugging approved November 16 19 59  
Plugging commenced November 16 19 59  
Plugging completed November 16 19 59  
Reason for abandonment of well or producing formation No commerical quantities of oil found.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4600 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 247'   |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set Bottom Plug at 550 feet with 20 sacks of cement;  
Second Plug set at 240' with 20 sacks of cement;  
Top Plug set at 35 feet with 10 sacks of cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 19 1960  
1-19-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
R. L. Bacon (employee of ~~owner~~ owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.  
(Signature) By: R. L. Bacon V-P  
780 Fourth National Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of January 19 60

Mona L. Laties

Notary Public.

My commission expires July 7, 1962

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita 2, Kansas

STATE CONSERVATION COMMISSION

JAN 19 1960

CONSERVATION DIVISION  
Wichita, Kansas

Wampler "A" No. 3  
C SW SE Sec. 17-21S-33W  
Finney, County, Kansas

Total Depth: 4600'

Commenced: 11-1-59 Completed: 11-16-59

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Elevation: 2897' K.B.  
Production: D & A

Casing Record: Set 8-5/8" Surface Pipe at 247' with 150 sacks cement.

Figures indicate bottom of formations:

|                      |       |                    | <u>tops</u> |         |
|----------------------|-------|--------------------|-------------|---------|
| Surface Clay         | 40'   |                    |             |         |
| Surface Sand & Clay  | 247'  | Hollenberg         | 2482'       | (/ 415) |
| Shale, Sand & Shells | 950'  | Herrington         | 2495'       | (/ 402) |
| Shale & Sand         | 1930' | Upper Krider       | 2521'       | (/ 376) |
| Shale & Shells       | 2022' | Lower Krider       | 2542'       | (/ 355) |
| Anhydrite            | 2037' | Winfield           | 2577'       | (/ 320) |
| Shale & Shells       | 2615' | Towanda            | 2639'       | (/ 258) |
| Shale & Lime         | 3760' | Fort Riley         | 2702'       | (/ 195) |
| Shale & Chalky Lime  | 3815' | Heebner            | 3780'       | - 883   |
| Shale & Lime         | 3870' | Toronto            | 3797'       | - 900   |
| Lime                 | 4600' | Lansing            | 3823'       | - 926   |
| Total Depth          | 4600' | Base Kansas City   | 4278'       | -1381   |
|                      |       | Marmaton           | 4293'       | -1396   |
|                      |       | Cherokee           | 4442'       | -1545   |
|                      |       | Morrow Shale       | 4583'       | -1686   |
|                      |       | Rotary Total Depth | 4600'       | (-1703) |

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *A. Brown*

Vice-President

Subscribed and sworn to before me this 27th day of November, 1959.

My Commission Expires:

July 7, 1962

*Mona L. Latier*  
Mona L. Latier-Notary Public