


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Finney County, Sec. 17 Twp. 21S Rge. 33W E/W
Location as "NE/CNW/SW" or footage from lines
C NE

Lease Owner The Maurice L. Brown Company
Lease Name Naiman Well No. 1
Office Address 200 Sutton Place, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Aug. 28 1979
Application for plugging filed(verbally) Aug. 28 1979
Application for plugging approved(verbally) Aug. 28 1979
Plugging commenced Aug. 28 1979
Plugging completed Aug. 28 1979
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Depth to top Bottom Total Depth of Well 2750'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

T.D. 2750'
Set 1st plug at 400' with 50 sacks
2nd plug at 40' solid bridge with 10 sacks
5 sacks in the rathole.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 1:15 p.m., 08-28-79

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc. SEP - 6 1979

STATE OF Kansas COUNTY OF Sedgwick
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 79



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

CONTRACTOR'S WELL LOG

15.055.20378.0000

OPERATOR: The Maurice L. Brown Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Naiman #1
 LOCATION: C NE, Section 17-21S-33W
 Finney County, Kansas
 SPUD DATE: August 20, 1979
 COMPLETION DATE: August 28, 1979

0	155	Shale and sand
155	1235	Sand and shale
1235	1965	Shale and sand
1965	2025	Shale
2025	2040	Anhydrite
2040	2553	Shale and lime
2553	2750	Lime and shale
	2750	Rotary Total Depth

Spud hole at 8:45 p.m., August 20, 1979. Drilled 373' of 12 1/4" hole. Ran 9 joints of 8-5/8" - 22.36# pipe. Set at 372' with 150 sacks of Halliburton lite, 1/4# flocel per sack, 2% Ca.Cl. followed with 150 sacks of Class H cement, 1/4# flocel per sack, 3% Ca.Cl. Cement did circulate. Plug was down at 9:00 a.m., August 21, 1979.

T.D. 2750'. Set 1st plug at 400' with 50 sacks, 2nd plug at 40' solid bridge with 10 sacks and 5 sacks in the rathole. Plug was down at 1:15 p.m., August 28, 1979.

SAMPLE TOPS:

Anhydrite 2025'
 B/Anhydrite 2040'

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

SEP - 6 1979

CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Naiman #1, C NE, Section 17-21S-33W, Finney County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 5th day of September, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.