


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

McPherson County. Sec. 9 Twp. 21S Rge. (E) 3 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE SE
Lease Owner Shell Oil Company
Lease Name J. Stucky Well No. 2
Office Address Box 426, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 6 19 30
Application for plugging filed August 27 19 53
Application for plugging approved August 31 19 53
Plugging commenced September 23 19 53
Plugging completed October 15 19 53
Reason for abandonment of well or producing formation Oil Depleted
If a producing well is abandoned, date of last production August 4 19 47
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Flat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Viola-Simpson-Arbuckle Depth to top 3303 Bottom 3333 Total Depth of Well 3404 Feet
Show depth and thickness of all water, oil and gas formations. 3333 3397 PB 3046

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola-Simpson	I.P. 1369 BQ NW, 24 hrs. swabbing	3303	3350	15 1/2" 8 5/8" 7"	150' 3260' 3303	None 2057' 2843
Viola-Simpson-Arbuckle	I.P. 488 BQ & 210 BW 24 hrs. pumping	3303	3404			
Mississippi	Dry	2975	2991			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PB from 3404 with cement and set limit plug at 3400.
Set lead plug at 3397. Dumped 4 sacks cement to 3388.
PB to 3364 with chat. Cleaned out to 3366.
PB with rock to 3305.
PB with cement to 3289.
PB with gravel to 3065.
PB with 4 sacks cement to 3046.

PB with 100' of rock and dumped 6 sacks cement to 2905.
Mudded hole, set rock bridge at 200' and dumped 20 sacks
cement. Mudded hole to 20' and dumped 10 sacks cement,
capping into bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Shell Oil Company
Address Box 426, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
B. V. Barker (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *B. V. Barker*
Box 426, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of December, 1953.

Betty Postlethwaite
Notary Public.

My commission expires April 16, 1956



SHELL-J. STUCKY #2
 NW SE SE 9-21S-3W
 Vosshell Field
 McPherson County, Kansas

CASING RECORD

0 - 40 surface
 130 quick sand
 150 sand
 495 sand & shale
 540 broken lime
 780 sandy lime
 930 broken lime & shale
 1100 shale
 1300 shale & limeshell
 1470 shale
 1580 shale & lime shells
 1600 lime & shale
 1730 shale
 1750 sandy lime
 1800 lime
 2005 sandy lime
 2045 lime
 2095 shale & lime shells
 2270 sand & shale
 2320 sand & lime
 2450 lime
 2485 sand & lime
 2550 shale & lime shells
 2670 lime
 2715 sand & lime
 2780 sand & shale
 2825 shale & shells
 2925 lime
 2945 sand & shale
 2965 shale
 2993 chat
 3035 lime
 3190 shale
 3260 sandy lime & shale
 3303 shale
 3333 lime
 3336 green shale, some sand
 3342 green sandy shale
 3350 sand
 3397 missing
 3404 dolomite TD
 3046 PB

15 1/2" cem 150 with 200 sax
 8 5/8" cem 3260 with 300 sax
 7" set 3303; shot at 3139, 3108 & 3080 - not free;
 perforated 1 hole at 2934 to test cement and
 perforated 48 holes 2975-2991 - dry.

PB with rock to 3305.
 PB with cement to 3289
 PB with gravel to 3065
 PB to 3046 with 4 sax cement

Formation Tops:

Mississippi Lime 2965
 Trenton 3303
 Decorah 3333
 Arbuckle 3397

RECEIVED
 DIVISION OF COMMISSIONERS
 AUG 25 1937
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 9-21S-3W
 BOOK PAGE 25 LINE 69