

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-159-21,464 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F.G. Holl Company, L.L.C. KCC LICENSE # 5056  
(owner/company name) (operator's)

6/03

ADDRESS 9431 E. Central, Suite 100 CITY Wichita

STATE Kansas ZIP CODE 67206-2543 CONTACT PHONE # (316) 684-8481

LEASE MITCHELL WELL# 1 SEC. 4 T. 21S R. 6 (East/West)

C. NE - NW - SPOT LOCATION/Q000 COUNTY Rice

600 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

600 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 8-5/8" SET AT 213'KB CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 3499' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3131'-3137' LKC

ELEVATION 1632'KB T.D. 3505' PPTD 3180' ANHYDRITE DEPTH 240'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, cement and plug according to KCC specifications.

RECEIVED

JUN 12 2003

(If additional space is needed attach separate page)

KCC WICHITA

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?           

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (620) 793-0195/(620) 786-5783 (cell)

ADDRESS P.O. BOX 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 31925

8/03

ADDRESS 410 West Main, Lyson, KS, 67554 PHONE # 620) 727-3410  
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 06/11/2003 AUTHORIZED OPERATOR/AGENT: Loveness Mpanje  
(signature)

# STERLING DRILLING CO.

15.159.21464.0000

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- MITCHELL #1  
Located: C NE NW, S ction 4-21S-6W, Rice County, Kansas

OWNER: Sher-Lon Corporation  
ROTARY DRILLING CONTRATOR: Sterling Drilling Company

COMMENCED: August 18, 1982  
COMPLETED: August 23, 1982

TOTAL DEPTH: 3500'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 60 Surface Soil and Sand	Ran 5 joints 8 5/8", 24# new casing.
60 - 160 Shale	201.46' set at 213' K.B. Cemented
160 - 216 Red Bed	with 150 sacks 50/50 Pozmix with
216 - 240 Shale	2% gel and 3% cc and 50 sacks Common
240 - 252 Anhydrite	with 3% cc. Plug down at 6:00 PM,
252 - 880 Shale	8-18-82, by Howco.
880 - 3125 Lime and Shale	
3125 - 3230 Lime	
3230 - 3500 Lime and Shale	Ran 85 joints 4 1/2", 10.5# new
	casing. 3505' pipe set at 3499' K.B.
	Cemented with 150 sacks 60/40 Pozmix with
	2% gel and 18% salt. Plug down at
	7:15 AM, 8-23-82, by Howco.

RECEIVED  
JUN 12 2003  
KCC WICHITA

Deviation Surveys: 1/2° at 1560'  
1 1/4° at 3500'



# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Holl, F.G., Company L.L.C.  
9431 E Central, Suite 100  
Wichita, KS 67206

June 13, 2003

Re: MITCHELL #1  
API 15-159-21464-00-00  
NENW 4-21S-6W, 660 FNL 660 FEL  
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #2  
130 S. Market, Room 2125  
Wichita, KS 67202-3208  
(316) 337-6231