

State of Kansas



15.075.30020-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Valintine of Livingston Oil Co. has this

date requested permission to plug the following described well:

Mr. Valintine guarantees payment of the plugging fee.

Operator's full Name: Livingston Oil Company

Complete Address: Box 1797, Tulsa, Oklahoma

Lease Name: Unit 3511-B Well No. 3511-B

Location: C NW SE Sec. 35 Twp. 21 Rge. 41 (E) (W)

County Hamilton Total Depth 2772' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Valintine was instructed to plug the well as follows:

8 5/8" to 169' circulated w/ cement. 4 1/2" to 2772' cemented.

Top perforations 2744' Plug bottom w/ 10 sacks cement.

Top of cement 2640' Mud 2640' to 600'

Spotted 25 sacks cement 600' to 500' Mud 500' to 170'

Spotted 20 sacks cement 170' to 110' Mud 110' to 404'

Plug, Huls& 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent