

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co. has this

date requested permission to plug the following described well:

Mr. MUSGROVE guarantees payment of the plugging fee.

Operator's full Name: Kern-Landes Exploration Co. Inc.

Complete Address: P. O. Box 699, Magnolia, Arkansas

Lease Name: Baier Well No. # 1

Location: C SE NE Sec. 34 Twp. 23 Rge. 20 (E) (W) W

County Edwards Total Depth 4745 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

274' of 8 5/8" surface pipe, cement circulated with 225

sacks. Fill hole with mud to 180', 1st cementing plug,

1/2 sack hulls, cement with 20 sacks. Fill hole with mud

to 40', 2nd cementing plug, 1/2 sack hulls, cement with 10

sacks to base cellar. Bridge and cement rat hole with 2

sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent