



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Julian of Murfin Drilling has this

date requested permission to plug the following described well:

Operator's Full Name: PETX CorporationComplete Address: 1020 Metro Bank Building, 475 17th Denver, Colorado 80202Lease Name: Wilson Well No. 1Location: C NE SW Sec. 18 Twp. 23 Rge. 20W (E) (W)County: Edwards Total Depth: 4750'Abandoned Oil Well Gas Well Input Well SWD Well D&A XXOther well as hereafter indicated: Mr. Julian was instructed to plug the well as follows:293' of 8 5/8Total of 110 sks of 50-50 poz-mix 6% gel 3% cc60 sks @ 900'35 sks @ 280'10 Sks @ 40' to 0Cemented by Sun5 rhPlugged by Tommy Thomas

RECEIVED
STATE CORPORATION COMMISSION

JUL - 2 1981

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Tommy Thomas
Conservation Division Agent