

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Elmer Rider of K & E Drilling Inc. has this

date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: Ferguson Oil Co.

Complete Address: 522 Union Center Bldg., Wichita, Kansas

Lease Name: Lippoldt Well No. # 1

Location: C SW NE Sec. 7 Twp. 23 Rge. 20 (E) (W) W

County Edwards Total Depth 4660 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

356' of 8 5/8" surface pipe, cement circulated. Fill hole
with drilling mud to 300', 1st cementing plug, bridged
with hulls, cemented with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, cement
with 10 sacks to base cellar. Rat hole bridged and cemented
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent