

15.047.00005.00.00

Form CP-3  
Rev. 6-26-62

40 KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

11-20-1964

NOV 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address: 1015 Union Center, Wichita, Kansas

Lease Name Groener Well No. # 1

Location C SE SE Sec. 5 Twp. 23 Rge. 20 (E) (W) W

County Edwards Total Depth 4617

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Apex Casing Pulling Co., Inc.

Address: 739 East Second St., Hoisington, Kansas License No. 544

Operation Completed: Hour 11:00AM Day 18th Month Nov. Year 1964

The Above well was plugged as follows:

375' of 8 5/8" surface pipe, cemented with 225 sacks. 4604' of 5 1/2" long string, cemented with 150 sacks. Top perforation 4504. Plug was pushed to 4500', and 20' of sand on plug, and cemented with 5 sacks. Fluid level in hole was at 60'. Bridge plug was pushed in fluid to 300', and 10' of rock bridge on plug at 300'. 8 sacks of cement was mixed in barrel and put on plug at 290', through the dump bailer. And let set over-night. Next morning hole was bailed dry, and 17 sacks of cement was added to plug.

Hole was filled with mud to 40', 10' of rock bridge, and cemented with 10 sacks to base cellar. 3700' of 5 1/2" long string was recovered from the hole. I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 11/20/64  
INV. NO. 195-W

Signed: Archie Elving  
Well Plugging Supervisor