

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Pawnee County, Sec. 1 Twp. 21S Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. NE SE NW

Lease Owner Vickers Explorations, Ltd.

Lease Name English Well No. 1

Office Address Box 2240 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed November 26 19 53

Application for plugging filed November 26 19 53

Application for plugging approved November 26 19 53

Plugging commenced November 26 19 53

Plugging completed November 26 19 53

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3620 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	852'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/ mud to 300', set plug @ 300' Dump 20 sx cement on plug.

Filled w/ mud to 40' Set plug @ 40' Dump 10 sx cement on plug.

STATE OF KANSAS  
CONSERVATION DIVISION  
WICHITA, KANSAS

1-15-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Drilling Co., Inc.

Address Box 2240 Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John M. Little (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little

Box 2240 Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4 day of December 19 53

Allen P. Denton

Notary Public.

My commission expires August 13, 1957

24-7368-S 3-53-20M

PLUGGING  
FILE SEC 1 T 21 R 15W  
PAGE 146 LINE 2

## VICKERS EXPLORATIONS, LTD.

English, Well #1  
NE SE NW Sec. 1-21S-15W  
Pawnee County, Kansas

Casing Record:  
8 5/8 " @ 852' w/ 400 sx.

Commenced: November 13, 1953  
Completed: November 26, 1953

Elevation: 1920 R. B.  
D. & A.

LOG

Surface Sand & Shale	0-270
Shale & Sand	270-420
Red Beds	420-849
Anhydrite	849-870
Red Beds, Shale & Shells	870-1365
Salt & Shale	1365-1650
Lime & Shale	1650-2370
Shale	2370-2540
Shale & Lime	2540-2632
Lime & Shale	2632-2733
Lime & Shale	2733-2888
Lime	2888-2914
Lime & Shale	2914-3053
Shale Black	3053-3057
Lime & Shale	3057-3161
Shale Black	3161-3165
Lime & Shale	3165-3175
Lime	3175-3195
Shale	3195-3263
Lime	3263-3268
Shale	3268-3271
Lime & Shale	3271-3528
Chert & Shale	3528-3554
Granite Wash	3554-3620 T.D.

Sample Markers:

Topeka	2888
Heebner	3161
Toronto	3175
Brown Lime	3263
Lansing	3271
Conglomerate	3528
Granite Wash	3554

D.S.T. 3349-3372 Fair steady blow, open  
1 hr. Recovered 175' salt water, F.P. 15#  
to 100# S.I.P. 1090#/20 min.

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

VICKERS EXPLORATIONS, LTD.

BY *Lyle D. Brown*

Sworn and subscribed to before me this 14 day of January, 1954.

My Commission Expires August 13, 1957.

*Allen P. Denton*  
Notary Public

STATE

CONFES

