

STATE OF KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION


FEB 4 1969

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 1 Twp. 21S Rge. (E) 15(W)
C S/2 S/2 NE
Location as "NE/CNWSW" or footage from lines
Lease Owner James D. Mooneyham
Lease Name Weathers Well No. 1
Office Address Box 111 Beverly, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 1-31 1969
Application for plugging filed 1-31 1969
Application for plugging approved 1-31 1969
Plugging commenced 4:30 PM 1-31- 1969
Plugging completed 5:45 PM 1-31 1969
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey - Hays, Kansas
Producing formation none Depth to top Bottom Total Depth of Well 3700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	890	8 5/8	888	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 275' Plug & Hulls @ 25 sx cement.
Filled to 40' Plug & Hulls Solid Bridge & 10 sx cement
2 sx in rat hole. Plugged at 5:45 PM

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor B & B Drilling, Inc.
Address 207 Petroleum Building- Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
207 Petroleum Building- Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 69

Alma A. Meiser

My commission expires May 31, 1970

Notary Public.

B & B DRILLING, INC.

548 Petroleum Building
Wichita, Kansas 67202

February 3, 1969

DRILLERS LOG

Re: Weathers #1
C S/2 S/2 NE Sec. 1-21S-15W
Pawnee County, Kansas

COMPANY: James D. Mooneyham
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3700'
COMMENCED: January 24, 1969
COMPLETED: January 31, 1969

0	180	Sand
180	313	Shale
313	411	Sand
411	515	Shale & Sand
515	566	Shale & Sand
566	830	Shale
830	879	Shale
879	890	Anhydrite
890	892	Anhydrite
892	975	Shale
975	1663	Shale
1663	1914	Shale & Lime
1914	2098	Lime & Shale
2098	2305	Shale & Lime
2305	2530	Shale & Lime
2530	2730	Shale
2730	2956	Lime & Shale
2956	3110	Shale
3110	3205	Lime
3205	3350	Lime & Shale
3350	3415	Lime
3415	3500	Lime
3500	3582	Lime
3582	3673	Lime
3673	3673	DST #1
3673	3700	Arbuckle
3700		Total Depth

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1969
CONSERVATION DIVISION
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the No.1 Weathers, located in Pawnee County, Kansas.

Bill Pahar President

Alma A. Meiser Notary Public

Subscribed and sworn to before me this 3rd day of February, 1969.

My commission expires May 31, 1970