

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Hodgeman

County, Sec. 17 Twp. 21S Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines C W2 NE SW
National Oil Company

Lease Owner National Oil Company

Lease Name BAUER HEIRS Well No. #1

Office Address 200 W. Douglas, Suite 550, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 08 1974

Application for plugging filed (verbal) December 08 1974

Application for plugging approved (verbal) December 08 1974

Plugging commenced December 08 1974

Plugging completed December 08 1974

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation Depth to top Bottom Total Depth of Well 4360 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug Set @ 850' with 60 Sacks Cement
2nd Plug Set @ 550' with 35 sacks cement
3rd Plug Set @ 45' with 15 Sacks Cement
Plugged rat hole with 2 sacks

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jerry A. Langrehr, V. P.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202 (Address)

11th day of December, 1974



Nancy E. Haner
Notary Public

RECEIVED
CORPORATION COMMISSION

DEC 12 1974

CONSERVATION DIVISION
Topeka, Kansas

CONTRACTOR'S WELL LOG

OPERATOR:	National Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	BAUER HEIRS #1
LOCATION:	C W/2 NE SW Sec. 17-21S-21W Hodgeman County, Kansas
SPUD DATE:	November 29, 1974
COMPLETION DATE:	December 8, 1974

0	110	Sand
110	178	Shale & Sand
178	310	Shale
310	1172	Shale & Sand
1172	2135	Shale
2135	3970	Shale & Lime
3970	4317	Lime
4317	4360	Mississippian Chert
	4360	Rotary Total Depth

Drilled 312' of 12 1/2" surface hole. Set 8 jts. used 8 5/8" @ 310'. Cemented with 225 sacks Common, 3% Ca.Cl. and 2% gel. Cement circulated.
 D & A: 1st Plug Set @ 850' with 60 sacks Cement; 2nd Plug Set @ 550' with 35 sacks Cement; 3rd Plug Set @ 45' with 15 sacks Cement; Plugged rat hole with 2 sacks. Cement; Plug was down @ 12:30 p.m. 12-08-74.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


Mr. Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BAUER HEIRS #1, C W/2 NE SW Section 17-21S-21W, Hodgeman County, Kansas

ABERCROMBIE DRILLING, INC.

By: *Jerry A. Langrehr*
 Jerry A. Langrehr, J.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of the 10th day of December, 1974.

Nancy E. Haner
 Nancy E. Haner - Notary Public



Commission Expires: April 8, 1978