


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 24 Twp. 21S Rge. 21W (X) (W)  
Location as "NE/CNW/SW" or footage from lines. NW SW SW  
Lease Owner Beacon Resources Corporation and Sterling Drilling Co.  
Lease Name Thompson Well No. 1  
Office Address P. O. Box 129, Sterling, Kansas 67579  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 23, 19 69  
Application for plugging filed December 22, 19 69  
Application for plugging approved December 22, 19 69  
Plugging commenced 7:30 PM, December 22, 19 69  
Plugging completed 2:30 AM, December 23, 19 69  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 1340' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	605'	None

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud. Plug at 589' with 50 sacks cement. Halls and bridge tamped with kelly at 40' and filled up cement to top. Made swadge and put 2" bull plug in top of it to stop movement of water.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company  
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner, (employee of owner) or (owner/proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 69

My commission expires \_\_\_\_\_  
BERNARD LAUDERMILK, Notary Public  
Commission Expires January 22, 1970

Bernard Laudermilk  
Bernard Laudermilk, Notary Public

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG - - - - - THOMPSON #1  
Located: NW SW SW, Section 24-21S-21W, Hodgeman County, Kansas

OWNER: Beacon Resources Corporation and Sterling Drilling Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 10, 1969

COMPLETED: December 23, 1969

TOTAL DEPTH: 4340'

<u>LOG</u>	
0 - 235	Surface Clay Sand
235 - 265	Blue Shale
265 - 500	Surface Shale
500 - 597	Shale
597 - 616	Anhydrite
616 - 935	Shale
935 - 1540	Shale - Red Rock
1540 - 1945	Shale and Red Bed
1945 - 2008	Shale and Lime
2008 - 3170	Lime
3170 - 3303	Shale
3303 - 3530	Lime
3530 - 3690	Shale and Lime
3690 - 4295	Lime
4295 - 4340	Miss.

CASING RECORD

Ran 8 5/8" Casing - Drilled 12 1/4" hole  
to 616'; ran 605' - 8 5/8" casing, cemented  
at 615' K.B. with 350 sacks Quikset. Plug  
down at 3:00 PM 12-11-69.

Plugged

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 31 1969  
CONSERVATION DIVISION  
Wichita, Kansas