

15.083.21023.0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 35 TWP. 21S RGE. 25 X/W
Location as in quarters or footage from lines:
SW NE NW

Lease Owner Vincent Oil Corporation
 Lease Name Five Star Farm Well No. #1
 Office Address 125 N. Market, Suite 1110 Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 12-16-82
 Application for plugging filed 12-16-82
 Plugging commenced 12-16-82
 Plugging completed 12-16-82
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4630'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	531'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Spot 60 sx. cement @ 960' thru drill pipe.
Spot 40 sx. cement @ 540' thru drill pipe.
Solid bridge plug, Spot 10 sx. cement @ 40' thru drill pipe.
Spot 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas #500 Wichita,
 (Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 27th day of December, 1982


My Commission expires:



Carolyn J. Tjaden
 Carolyn J. Tjaden, Notary Public.
 STATE CORPORATION COMMISSION

DEC 28 1982

CONSERVATION DIVISION
Wichita Kansas



15.083.21023.0000

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Vincent Oil Corporation 1110 Bitting Bldg. Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202Lease Name Five Star Farm Well No. #1Sec. 35 T. 21S R. 25W Spot SW NE NWCounty Hodgeman State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 531' with 260 sx. 3%cc
2%gel

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4630'Drilling Commenced 12-4-82 Drilling Completed 12-16-82

Formation	From	To	Tops
Cellar	0	7	Anhydrite 1660
Sand, Shale	7	905	Lansing 3880
Shale, Lime, Sand	905	1555	Mississippi 4554
Shale	1555	1660	
Shale, Lime	1660	3271	
Shale	3271	3363	
Lime, Shale	3363	3525	
Shale, Lime	3525	3880	
Lime	3880	4060	
Shale, Lime	4060	4564	
Lime, Shale	4564	4581	
Lime	4581	4630	