

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Hodgeman County, Sec. 30 Twp. 21S Rge. 25 (E)W (W)

Location as "NE/CNWxSWx" or footage from lines. C SE SE
Lease Owner. Pickrell Drilling Company
Lease Name. Sinclair "C" Well No. 1
Office Address. 705 Fourth National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. October 21 19 71
Application for plugging filed. October 21 19 71
Application for plugging approved. October 21 19 71
Plugging commenced. October 21 19 71
Plugging completed. October 21 19 71
Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Edgar J. Eves
Producing formation. Depth to top. Bottom. Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 700' w/100 sacks cement,
plug @ 240' w/30 sacks and plug @ 45'
w/10 sacks.


RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor. Pickrell Drilling Company
Address. 705 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well to be filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)



Subscribed and sworn to before me this 27th day of October, 1971.
Ruth M. Sullivan
Notary Public.
My commission expires August 13, 1973

ROTARY DRILLING LOG

15.083-20189-0000

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Building
 Wichita, Kansas
 LOCATION: Sinclair "C" No. 1, C SE SE Sec. 30-21S-25W
 Hodgeman County, Kansas

Rotary Drilling Commenced 10/9/71
 Rotary Drilling Completed 10/21/71

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: Run 10 Jts. 8 5/8" surface casing set @ 261' KB. Cemented with 150 sacks cement. Completed 8:30 P.M., October 9, 1971.
 No oil string run. D & A, Plugged 5:00 A.M., October 21, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)


45	Post Rock - Clay		CFS.
265	Shale & Sand		<u>3825</u>
1110	Shale		3860
1310	Sand		3895
1470	Shale		3940
1618	Shale & Lime		3955
1652	Anhydrite		4015
1970	Shale		4050
2340	Shale & Lime		4125
2610	Shale & Lime Stringers		4270
2740	Lime & Shale		4365
2895	Shale & Lime		4385
2970	Lime & Shale		4450
3170	Shale & Lime		4475
3355	Lime & Shale		4540
3690	Shale & Sandy Lime		4550
3750	Shale & Lime		
3898	Lime & Shale		
3940	Shale & Lime		
4065	Lime & Shale		
4120	Shale & Lime		
4151	Lime	Board	<u>S.L.M.</u> <u>3693.21</u>
4205	Shale & Lime	Strap	<u>3691.21</u>
4295	Lime & Shale		2.00 Difference
4340	Shale & Lime		
4385	Lime & Shale		
4479	Shale & Lime		
4550	Mississippi, RTD		

Slope Tests
 2000
 2500
 3000
 3500
 4000
 4500

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 29 1971
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By C. W. Sebitts Attorney-in-Fact



On this 27th day of October, 1971, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

My commission expires: August 13, 1973

Ruth M. Sullivan
 Ruth M. Sullivan Notary Public