


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Rice County, Sec. 19 Twp. 21 Rge. 7 (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner M.D.I.C., Inc.
Lease Name Swartz #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/6/76 19
Plugging completed 2/10/76 19
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	218	none
				5 1/2"	3479	2985

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3300' and ran 4 sacks cement. Loaded hole, shot pipe at 2974', pulled 88 joints. Set rockbridge from 290 to 270' and ran 4 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*
CHASE, KANSAS

Subscribed and Sworn to before me this 10th day of February, 1976

My commission expires *Margaret Melche*
Notary Public



15-159-30322-0000

RICHARD G. SMITH
PETROLEUM GEOLOGIST

WICHITA 2, KANSAS

602 Rule Bldg.

August 4, 1966

D-1111-5-9626
R.L. MUZ 0271

Triple "D" Drilling Company
2400 North Main
Hutchinson, Kansas

Re: Triple "D" Drilling Company
No. 1 Swartz
C NW SE Sec. 19, T1 S., R. 7 W.
Rice County, Kansas

Gentlemen:

The following is my interpretation of the geological data derived from the samples, drilling time log, and electrical log on the No. 1 Swartz.

FORMATION TOPS

	Samples	Electrical Log
Heebner	2762	2762
Toronto	2730	2732
Douglas	2703	2703
Brown Line	2671	2671
Lansing	2046	2048
Base Kansas City	3306	3306
Shaley Conglomerate	3368	3368
Cherty Conglomerate	3331	3332
Mississippian	3412	3414
Kinderhook	3450	3452
Rotary Total Depth	3430	3430

REGIONAL STRUCTURAL CORRELATION

5 1/2 casing at 3479

Formation	Triple "D" No. 1 Swartz C NW SE 19-21-7	Triple "D" No. 1 Barber C NE SW 19-21-7 O.P.
Lansing	-1424	-1424
Cherty Conglomerate	-1783	-1783
Mississippian	-1790	-1777
Total Depth	-1858	-1851

(Note: Elevation estimated to be same on Swartz, as on Barber No. 1)

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1976

CONSERVATION DIVISION
Wichita, Kansas