


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rice County, Sec. 19 Twp. 21 Rge. 7 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NW NE  
Lease Owner Sterling Drilling Co.  
Lease Name Barber #2 Well No. \_\_\_\_\_  
Office Address Sterling, Kansas 67579  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 1/14/80 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 1/18/80 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3389'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	172	none
				5 1/2"	3388	2813'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Sanded to 3300' and ran 5 sacks cement. Loaded hole with salt water, shot pipe at 2875', 2814'  
and pulled 90 joints. Set rock bridge at 300' and ran 5 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 24 1980

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of Jan., 19 80

[Signature]  
Notary Public.

My commission expires \_\_\_\_\_



STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- BARBER #2

Located: C NW NE, Section 19-21S-7W, Rice County, Kansas

OWNER: Sterling Drilling Company and Martin Oil and Gas Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

Commenced: July 25, 1972  
Completed: July 30, 1972

TOTAL DEPTH: 3389'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 186 Sand and Shale	Ran 4 joints 8 5/8" OD surface casing, 169.18' cemented at 172' K.B. with 175 sacks 60/40 Pozmix with 3% HA-5. Plug down 7:00 PM, 7-25-72.
186 - 765 Shale	
765 - 1275 Shale, Limed salt	
1275 - 3127 Lime and Shale	Ran 109 joints 5 1/2" 11# 8rd casing total pipe threads off 3396.20', set at 3388' with 100 cu. ft. salt saturated Pozmix. Plug down 7:30 AM, 7-30-72.
3127 - 3260 Lime	
3260 - 3389 Lime and Shale	

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 1970

CONSERVATION DIVISION  
Wichita, Kansas