

ATE OF KANSAS  
ATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
Chicago, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-20,203-0000

LEASE NAME Ball

WELL NUMBER #1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18 TWP. 21 SRGE. 7W (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-22-98

Plugging Completed 10-23-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

*Recd  
10-23-98*

EASE OPERATOR Te-Pe Oil & Gas

DRESS P.O. Box 522 Canton, Ks. 67428

PHONE# (316) 628-4428 OPERATORS LICENSE NO. 5920

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom P.O. 3440

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	250'	None
				5-1/2"	3439'	1000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Bottom plugged with sand to 3250' and 5 sks. cement. Shot pipe @2400', 2200', 2000', 1800', 1600', 1400', 1000', spotted 35 sks. cement @1000', pulled to 650', pumped 35 sks. cement, pulled to 300', pumped 90 sks. cement and circulated to surface, 60/40 pos, 4% gel.  
Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Te-Pe Oil & Gas

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1998

*Irene Herzberg*  
Notary Public

My Commission Expires: \_\_\_\_\_

