

15.113-05975.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Schroeder Unit

WELL NUMBER #3

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 32 TWP. 21 RGE. 3 (E) or (W)

COUNTY McPherson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Brunson Production, Inc.

ADDRESS 125 N. Emporia, Suite 200, Wichita, KS 67202

PHONE# (316) 264-3781 OPERATORS LICENSE NO. 5350

Date Well Completed _____

Character of Well T&A

Plugging Commenced 8/25/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/25/89

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #2, Merlin Unruh

is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Hunton Depth to Top 3435 Bottom 3437 T.D. 3437

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	287'	0
				5-1/2"	3436'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Ran tbg. to 3306'. Spot 50 sx. cement @ 3306'. Pull tbg. to 2750'. Mixed 25 sx. gel and 15 sx. hulls, circulate to surface. Pull tbg. to 400', mixed 50 sx. circulate cement, pull tbg. and fill to top w/ cement. Pump in surface pipe, fill to surface, cement circulated on outside of surface pipe. Finished 8/25/89. 9/28/89 In digging down to cut off the surface pipe we (back)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Agent W. S. Brunson License No. _____

Address 125 N. Emporia, Suite 200, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

W. S. Brunson, Agent for _____ (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W. S. Brunson

6-5-89

RECEIVED
STATE CORPORATION COMMISSION

Address) 125 N. Emporia, Suite 200

Wichita, KS 67202


SUBSCRIBED AND SWORN to before me this 3rd day of October, 19 89

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: June 9, 1993

Pearl E. Craytor
Notary Public
Pearl E. Craytor

discovered that a port hole in the braden head was not plugged. Hence, the reason for the cement to circulate on outside of pipe. In checking we found the cement @ 29' in the annulus space and at 65' in the $5\frac{1}{2}$ ". Filled both with redimix cement to the surface. Job complete.



15 43.05975.0000

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS

February 10, 1965

COMPANY: DRUMSON-SPINES
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: DAVE J. SCHROEDER #1
 LOCATION: SE/4 NE/4 SE/4, Sec. 32-21-3W,
 McPherson County, Kansas
 COMMENCED: February 3, 1965
 COMPLETED: February 9, 1965
 ELEVATION:

0	to	38	Clay
35	to	200	Sand
200	to	750	Shale
750	to	790	Lime & Shale
790	to	1060	Lime
1060	to	1790	Lime & Shale
1790	to	2085	Shale & Lime
2085	to	2215	Lime
2215	to	2400	Lime & Sand
2400	to	2490	Lime & Shale
2490	to	2850	Lime
2850	to	2985	Lime & Shale
2985	to	3132	Shale & Lime
3132	to	3305	Mississippi
3305	to	3385	Shale & Lime
3385	to	3437	Shale
		3437	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 6 1989
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 12 1/4 in. hole to 287 ft. and run 289.30 ft. of 5 5/8 in. casing and set on bottom at 287 ft. with 225 sack cement and 3% Calcium Chloride. Plug down at 2:00 P.M., February 3, 1965. Cut 7 7/8 in. hole to 3437 ft. and run 3444.09 ft. of 5 1/2 in. O.D. casing. Cemented on bottom at 3436 ft. with 100 sacks salt saturated cement. Plug down at 7:00 P.M., February 9, 1965. Shoe Joint 22.24ft.

TOPS: Mississippi - 3132' Wisner - 3433' Hunton - 3455'

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Dave J. Schroeder #1, located on the SE/4 NE/4 SE/4 of Sec. 32-21-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

[Signature]
 Charles D. Johnson, Sec'y.-Treas.

Subscribed and sworn to before me a notary public in and for McPherson County, Kansas this 10th day of February, 1965.

[Signature]
 Ruth McVay - Notary Public

My Commission Expires: December 16, 1965.