

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County, Sec. 32 Twp. 21 Rge. 3 (E) (W) X

Location as "NE/CNW&SW" or footage from lines SE/4-NE/4-SE/4 SE SE NE  
Lease Owner Brunson-Spines  
Lease Name Goertzen Well No. 1  
Office Address 800 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed September 27, 19 66  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 19  
Plugging completed September 27, 19 66  
Reason for abandonment of well or producing formation Hole dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, McPherson, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0	30'			
Sand		30'	180'			
Shale		180'	232'	13"	232'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug at 300 ft. with wooden plug and rock to 270 ft. and cemented with 50 sacks cement to 200 ft. Plugging completed by 9:00 P.M., September 27, 1966 by State Plugger, Hugh Scott, McPherson, Kansas.

10-7-1966  
RECEIVED  
STATE CORPORATION COMMISSION  
OCT 7 1966  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.  
Address Box # 455, McPherson, Kansas 67460

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
W. S. Bill Brunson (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W.S. Brunson

800 Wichita Plaza, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of October, 1966

My commission expires June 9, 1969

Pearl E. Craytor  
Notary Public.



15-113-30149-0000

# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS  
67460

September 28, 1966

COMPANY: BRUNSON-SPINES  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: GOERTZEN #1  
 LOCATION: SE 1/4 NE 1/4 SE 1/4 of Sec. 32-21-3,  
 McPherson, County, Kansas  
 COMMENCED: September 20, 1966  
 COMPLETED: September 27, 1966  
 ELEVATION: 1466 K. B.

0	to	30	Clay
30	to	180	Sand
180	to	580	Shale
580	to	895	Shale & Lime
895	to	1045	Lime
1045	to	1780	Shale & Lime
1780	to	2175	Lime & Shale
2175	to	2435	Shale & Lime
2435	to	2920	Lime
2920	to	3065	Lime & Shale
3065	to	3115	Shale
3115	to	3170	Mississippi Chert
3170	to	3265	Mississippi
3265	to	3270	Lime
3270	to	3542	Shale
3542	to	3563	Viola
		3563	T. D.

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 7 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas

Cut 17 1/4 in. hole to 232 ft. and run 240 ft. of 13 in. surface pipe and cemented with 225 sacks cement on bottom at 232 ft. Plug down at 1:45 P.M., September 20, 1966. Cut 7 7/8 in. hole to 3563. Hole dry and abandoned. Set bottom plug at 300 ft. with wooden plug and rock to 270 ft. and cemented with 50 sacks cement to 200 ft. Plugging completed by 9:00 P.M., September 27, 1966 by State Plugger, Hugh Scott, McPherson, Kansas.

TOPS: Mississippi - 3115' Viola - 3542'

Measurements taken from K. B.

### CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Goertzen #1, located on the SE 1/4 NE 1/4 SE 1/4 of Sec. 32-21-3, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*H. J. Plouffe*  
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 29<sup>th</sup> day of September, 1966.

*Ruth McVay*  
 Ruth McVay - Notary Public

My Commission Expires: December 10, 1969.